



S.M.C

Group rating factors for more than one twin or multicore armored or unarmored cables in horizontal formation laid in direct ground.

No. of cables	2	3	4	5	6	7	8	9	10	11	12
Cables laid touching	0.81	0.7	0.63	0.59	0.55	0.52	0.5	0.48	0.47	0.45	0.44
Cables laid 15 cm apart	0.87	0.78	0.74	0.70	0.68	0.66	0.64	0.63	0.62	0.61	0.6
Cables laid 30 cm apart	0.91	0.84	0.81	0.78	0.77	0.75	0.75	0.74	0.73	0.73	0.72
Cables laid 45 cm apart	0.93	0.88	0.86	0.84	0.83	0.82	0.81	0.81	0.8	0.8	0.8
Cables laid 60 cm apart	0.95	0.9	0.89	0.87	0.87	0.86	0.86	0.85	0.85	0.85	0.84