



S.M.C

Group rating factors for more than three single core cables laid in conduits buried in concrete, on surface of wall, in trunking, racks.

No. of Load conductors	4	6	8	10	12	16	20	24	28	32	36	40
Correction Factors	0.8	0.69	0.62	0.59	0.55	0.51	0.48	0.43	0.41	0.39	0.38	0.36